

UNOFFICIAL COPY OF THE CONTRACT DOCUMENTS FOR THE PROJECT

GRAPH

SIOW: ad-c-32a Plastic emulsion paint [edit] [delete]

Start: 15-02-2017; Finish: 31-12-2021; Duration: 1781 days

Qty: 13515 sqmAdd Resources

Code	Item Description	Unit	Approved			Work Progress 13,515 sqm (100%)	Revised		
			Qty	Rate	Amount		Qty	Rate	Amount
05-03-058	Chalk Powder, Market	Kg	0	0	0	0	2	16	32
10-04-041	Plastic Paint, ivory	Ltr	0	0	0	0	15	0	227.78
10-04-042	Plastic Paint, white	Ltr	0	0	0	0	15	0	233.33
10-04-051	Putty, wall	Ltr	0	0	0	0	15	0	77.78
10-40-040	Formica,	Nos	0	0	0	0	1	0	50
14-01-008	Painting Brush, 50mm	Nos	0	0	0	0	2	62.5	125
14-01-011	Painting Brush, 100mm	Nos	0	0	0	0	2	40	80
14-03-004	Roller Painting Brush, 150mm	Nos	0	0	0	0	2	120	240
14-03-036	Foam Roller Brush, 300mm	Nos	0	0	0	0	2	0	0
14-06-012	Water Paper No. 120,	Nos	0	0	0	0	2	25	50
14-10-001	Markin Cloth, All Variety	M	0	0	0	0	2	15	30
38-28-051	Scraper, 100mm	Hr	0:00	0	0	0	2	0.4	0.8
99-09-003	Plastic Paint (Material +Labor) ,	M²	4950	129.12	639144	4950	4950	129.12	639144
SIOW Direct Expenses Rate Tk. 47.29/sqm							Sub Total Amount: Tk.639144		
SIOW Direct Expenses Rate Tk. 47.33/sqm							Sub Total Amount: Tk.639701.8		

Update

Estimated Direct Expenses: Total Tk. 639144 (81%)

Material Tk. 0 (0%);

Estimated Item of Work Direct Expense is Tk.47.29/sqm

Equipment and Tools Tk. 0 (0%);

Labour Tk.639144 (81%)